

																												
2017 Arterial Street Crack Seal Project																												
BID TABULATION - FINAL																												
Bid Date: March 28, 2017, 2:00PM			Huizenga Enterprises LLC			Asphalt Quality Sealers			Doolittle Construction LLC			C.R. Contracting LLC			Highline Pavement Maintenance Inc.		JAG Corp		JNR Paving Inc.		Evergreen Asphalt & Concrete Inc.		Combined Construction Inc.		Combined Construction Inc.		Tony Lind Paving LLC	
By: Mark A. Freiberger, PE, Director of PW																												
		Bellingham, WA				Anacortes, WA		Bellevue, WA		Bend, OR		Mount Vernon, WA		Tulalip, WA		Sedro-Woolley, WA		Kent, WA		Mukilteo, WA		Mukilteo, WA		Kent, WA				
	QUANT	UNIT	RATE	TOTAL	RATE	TOTAL	RATE	TOTAL	RATE	TOTAL	RATE	TOTAL	RATE	TOTAL	RATE	TOTAL	RATE	TOTAL	RATE	TOTAL	RATE	TOTAL	RATE	TOTAL				
1. Crack Seal	20,000	LF	1.24	24,800.00	1.12	22,400.00	1.35	27,000.00	1.25	25,000.00	1.43	28,644.00	1.76	35,200.00	2.01	40,145.00	1.92	38,400.00	2.00	40,000.00	2.50	50,000.00	2.50	50,000.00				
2. Crack Seal w/ Routing	10,000	LF	1.24	12,400.00	1.57	15,700.00	1.77	17,700.00	2.17	21,700.00	2.88	28,752.50	2.47	24,700.00	2.12	21,157.75	2.47	24,700.00	2.50	25,000.00	3.00	30,000.00	3.25	32,500.00				
<b>TOTAL</b>				<b>37,200.00</b>		<b>38,100.00</b>		<b>44,700.00</b>		<b>46,700.00</b>		<b>57,396.50</b>		<b>59,900.00</b>		<b>61,302.75</b>		<b>63,100.00</b>		<b>65,000.00</b>		<b>80,000.00</b>		<b>82,500.00</b>				
<b>POSITION</b>			<b>Low</b>		<b>2</b>		<b>3</b>		<b>4</b>		<b>5</b>		<b>6</b>		<b>7</b>		<b>8</b>		<b>9</b>		<b>10</b>		<b>11</b>					
Corrections made to calculations			None		Yes		No		No		Yes		No		Yes		No		No		No		No					
MRSC			Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes					
Statement of Bidder's Qualifications			Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes					
Addendum 1 Noted			Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes		Yes					
<b>NOTES</b>																												
1. Prices include sales tax, freight, all licenses, permits, fees etc. not otherwise specifically mentioned.												Corrected - Bid note: bid prices are pre-tax		Rates did not include sales tax														
2. Project assumes 30,000 LF will be cracked sealed. Based on bid prices this amount may vary. No guarantee is made of the actual value of the work.																												
3. Item 1 Crack Seal item without routing is per the Simple Band Aid method.																												
4. Item 2 Crack Seal item with routing to provide a 3/4" reservoir width and 3/4" depth per the Standard Recessed Band-Aid method																												
5. All cracks to be cleaned prior to sealing using the Hot Compressed Air Lance method.																												