

City of Sedro-Woolley

ADDENDUM NO. 4

TO THE PLANS, SPECIFICATIONS, PROPOSAL AND CONTRACT FOR THE CITY OF SEDRO-WOOLLEY

Fruitdale Road Arterial Improvement
TIB Project No. 8-2-126(011)-1
Sedro-Woolley Project No. 2018-PW-01

Addendum Issued: March 7, 2018
Date of Bid Opening: March 13, 2018



TO ALL PLAN HOLDERS:

You are hereby notified of the following changes, revisions, deletions additions, corrections and/or clarifications to the plans, specifications, and contract documents for the Fruitdale Road Arterial Improvement Project. This addendum is made part of these contract documents as though it was originally included in the Contract. The Contractor shall acknowledge receipt and understanding of the Addenda in the Contract Proposal, page D-9.

I. ADDITIONS, MODIFICATIONS, AND/OR DELETIONS TO THE PROPOSAL

ITEM NO. 1:

Bid Schedule – Base Bid, pages D-3 to D-8

Delete Base Bid Schedule pages D-3 to D-8 and replace them with attached.

II. ADDITIONS, MODIFICATIONS, AND/OR DELETIONS TO THE SPECIAL PROVISIONS

ITEM NO. 2:

Special Provisions, Section 8-21.3(14) Sign and Concrete Base Fabrication and Installation

Supplement Section 8-21.3(14), as revised by Addendum No. 3 with the following:

The right side aluminum panels of both signs and the left side of the “Port of Skagit” sign shall be painted solid colors matching the green or the blue primary color of the sign front face. The left panel of the “Swift Center” sign shall be colored per the conceptual drawings in Appendix H of the contract documents.

Both the front and back aluminum panels shall contain graphics and lettering consistent with the conceptual drawings in Appendix H of the contract documents.

Final location of the Sift Center signs shall be determined by the Owner.

Internal framing shall be comprised of steel or aluminum reinforcing brackets.

BID SCHEDULE

Fruitdale Road Arterial Improvement Project (Base Bid)

NOTE: Unit prices for all items, all extensions, and the total amount bid must be shown. All entries must be typed or entered in ink.

Item No.	Spec. Section	Item	Unit	Quantity	Unit Price	Total Amount
1	1-09.7	Mobilization	LS	1		
2	1-07	SPCC Plan	LS	1		
3	1-07	Potholing	FA	10,000	\$1.00	\$10,000
4	1-10	Flaggers	HOUR	1,280		
5	1-10	Traffic Control Supervisor	LS	1		
6	1-10	Project Temporary Traffic Control	LS	1		
7	1-10	Other Traffic Control Labor	HR	250		
8	2-01	Clearing and Grubbing	LS	1		
9	2-02	Removal of Structures and Obstruction	LS	1		
10	2-03	Roadway Excavation Incl. Haul	CY	1,930		
11	2-03	Unsuitable Foundation Excavation Incl. Haul	CY	400		
12	2-03	Ditch Excavation Incl. Haul	CY	216		
13	2-11	Trimming and Cleanup	LS	1		
14	2-11	Repair Public & Private Facilities	FA	20,000	\$1.00	\$20,000
15	4-02	Gravel Base Incl. Haul	TON	6,200		
16	4-04	Crushed Surfacing Base Course	TON	1,173		
17	4-04	Crushed Surfacing Top Course	TON	605		
18	5-04	HMA CL 1/2 In. PG 64-22	TON	2,908		
19	5-04	Commercial HMA	TON	30		

NOTE: Unit prices for all items, all extensions, and the total amount bid must be shown. All entries must be typed or entered in ink.

Item No.	Spec. Section	Item	Unit	Quantity	Unit Price	Total Amount
20	5-04	Asphalt Cost Price Adjustment	CALC	1	EST	\$5,000
21	5-04	Planing Bituminous Pavement	SY	4,570		
22**	5-05	Textured & Pigmented Cement Concrete Pavement (9" Central and Splitter Island)	SY	224		
23	2-02	Roadway Repair	SY	60		
24	6-13	Structural Earth Wall	SF	1,385		
25**	6-13	Geogrid for MSE Roadway Repair	SY	2,270		
26	7-01	Underdrain Pipe 4 In. Diam.	LF	507		
27*	7-01	Drain Pipe 4 In. Diam.	LF	20		
28	7-04	Schedule A Storm Sewer Pipe 8 In. Diam.	LF	238		
29*	7-04	Schedule A Storm Sewer Pipe 12 In. Diam.	LF	1,035		
30	7-04	High-Density Polyethylene (HDPE) Pipe 18 In. Diam.	LF	177		
31	7-04	Profile Wall PVC Culvert Pipe 24 In. Diam.	LF	46		
32	7-04	Ductile Iron Storm Sewer Pipe 12 In. Diam.	LF	124		
33	7-05	Catch Basin Type 1	EA	17		
34	7-05	Adjust Catch Basin	EA	3		
35*	7-05	Concrete Inlet	EA	4		
36	7-05	Trash Rack	EA	1		
37	7-08	Trench Excavation Safety System	LS	1		
38	7-08	Trench Over-Excavation	CY	150		
39	7-08	Foundation Material	TON	280		
40	7-12	Adjust Existing Valve Box	EA	22		
41	7-12	Adjust Existing Water Meter Box	EA	4		
42	8-01	ESC Lead	DAY	20		
43	8-01	Inlet Protection	EA	13		

NOTE: Unit prices for all items, all extensions, and the total amount bid must be shown. All entries must be typed or entered in ink.

Item No.	Spec. Section	Item	Unit	Quantity	Unit Price	Total Amount
44	8-01	Silt Fence	LF	4,700		
45	8-01	Storm Water Pollution Prevention Plan	LS	1		
46	8-01	Erosion/Water Pollution Control	FA	10,000	\$1.00	\$10,000
47	8-01	Seeding, Fertilizing and Mulching	AC	2		
48	8-01	Street Cleaning	Hour	200		
49	8-01	Biodegradable Erosion Control Blanket	SY	1,860		
50	8-02	Topsoil Type A	CY	100		
51	8-02	Weed Barrier Mat	SF	775		
52	8-02	PSIPE Prunus cerasifera 6' to 7'	EA	3		
53	8-02	PSIPE Acer rubrum 6' to 7'	EA	3		
54	8-02	Streambed Cobbles	TON	70		
55	8-02	Streambed Boulders	EA	50		
56	8-15	Quarry Spalls	CY	30		
57	8-04	Cement Conc. Traffic Curb and Gutter	LF	2,894		
58	8-04	Extruded Curb	LF	200		
59	8-04	Roundabout Truck Apron Cement Conc. Curb	LF	489		
60	8-04	Roundabout Cement Conc. Curb and Gutter	LF	416		
61	8-06	Cement Concrete Driveway, Type 1	SY	184		
62	8-13	Monument Case & Cover	EA	6		
63	8-14	Cement Conc. Sidewalk	SY	2,233		
64	8-14	Cement Conc. Curb Ramp Type Parallel A	EA	3		
65	8-14	Cement Conc. Curb Ramp Type Combination	EA	5		
66	8-14	Cement Conc. Curb Ramp Type Perpendicular	EA	5		
67	8-11	Beam Guardrail Type 31	LF	920		
68	8-18	Mailbox Support Type 2	EA	7		
69	8-20	Conduit Pipe 2 In. Diam.	LF	120		

NOTE: Unit prices for all items, all extensions, and the total amount bid must be shown. All entries must be typed or entered in ink.

Item No.	Spec. Section	Item	Unit	Quantity	Unit Price	Total Amount
70*	8-20	Luminaire Foundation Form 30" Diam.	EA	1		
71	8-20	Rotating Rectangular Flashing Beacon	EA	2		
72	8-21	Permanent Signing	LS	1		
73**	8-21	Swift Center Signage	LS	1		
74	8-22	Type D Plastic (MMA) Double Yellow Center Line	LF	3,360		
75	8-22	Type D Plastic (MMA) Yellow Wide lane Line	LF	450		
76	8-22	Type D Plastic (MMA) White Edge Lane Line	LF	2,200		
77	8-22	Type A Plastic Crosswalk	SF	950		
78	8-22	Type D Plastic (MMA) White Wide Line	LF	135		
79	8-22	Plastic Yield Line Symbol	EA	15		
80	8-22	Plastic Stop Line	LF	44		
81	8-23	Temporary Pavement Marking - Short Duration	LF	1,500		
82	8-23	Removing Temporary Pavement Marking	LF	1,500		
83	8-24	Rock Wall	SF	364		
84	8-25	Pedestrian Railing	LF	50		
85	8-26	Rockery Wall Relocation	LF	400		
Bid Amount - Base Bid					\$	

All applicable sales tax shall be included in the bid price per APWA GSP 1-07.2 Rule 171 and WAC 458-20-171.

**Fruitdale Road Arterial Improvement Project
Sanitary Sewer Improvements (Schedule A)**

NOTE: Unit prices for all items, all extensions, and the total amount bid must be shown. All entries must be typed or entered in ink.

Item No.	Spec. Section	Item	Unit	Quantity	Unit Price	Total Amount
A-1	1-09	Mobilization	LS	1		
A-2	1-07	Potholing	FA	2,500	\$1.00	\$2,500
A-3	7-05	Manhole 48 In. Diam. Type 1	EA	3		
A-4	7-05	Adjust Manhole	EA	1		
A-5	7-05	Drop Manhole Connection	EA	2		
A-6	7-08	Trench Excavation Safety System	LS	1		
A-7	7-08	Trench Over-Excavation	CY	50		
A-8	7-08	Foundation Material	TON	96		
A-9	7-17	PVC Sanitary Sewer Pipe 8-In. Diam.	LF	445		
A-10	7-17	PVC Sanitary Sewer Pipe 6-In. Diam.	LF	130		
A-11	7-18	Side Service	EA	4		
A-12	7-19	Sewer Cleanout	EA	6		

Sub-Total - Schedule A	\$
Sales Tax, 8.5%	\$
Total – Schedule A	\$

**Fruitdale Road Arterial Improvement Project
Communication Conduit (Schedule B)**

NOTE: Unit prices for all items, all extensions, and the total amount bid must be shown. All entries must be typed or entered in ink.

Item No.	Spec. Section	Item	Unit	Quantity	Unit Price	Total Amount
B-1	8-20	Conduit Pipe 4 In. Diam.	LF	2,120		

Sub-Total - Schedule B	_____	\$	_____
Sales Tax, 8.5%	_____	\$	_____
Total – Schedule B	_____	\$	_____

Bid Schedule Totals

Bid Amount: Base Bid: _____

Bid Amount: Schedule A: _____

Bid Amount: Schedule B: _____

Total Bid Amount: Base Bid + Schedule A + Schedule B: _____